

Water Treatment Installations and Equipment Provided by Krudico, Inc.



Provided and Installed Krudico Systems



Provided Krudico Systems Only



Installation of Systems Only

Customer	System Type	Flow Rate (GPM)	Valve Type	Controller
City of Early, IA	Provided and Installed Ion Exchange For Nitrate Reduction	75	Two (2) Fleck 3900 Multi-Port Control Valves	Demand Reset Meter
City of Ute, IA	Provided and Installed Ion Exchange for Nitrate Reduction	70	Three (3) Fleck 2900 Multi-Port Control Valves	Demand Reset Meter
City of Harvey, IA	Provided Iron/Manganese Filtration and Ion Exchange for Softening	50	Four (4) Fleck 2900 Multi-Port Control Valves	Demand Reset Meter
City of Gilmore City, IA	Provide and installed Ion Exchange for Nitrate Reduction	150	Three (3) Fleck 3900 Multi-Port Control Valves	Demand Reset Meter
City of Auburn, IA	Refurbished Existing Ion Exchange/Softening Iron/Manganese Filtration	100	Aqua Matic Diaphragm Valves	Demand Reset Meter
City of Sioux Rapids, IA	Provided and Installed Ion Exchange for Nitrate Reduction	150	Three (3) Fleck 3900 Multi-Port Control Valves	Demand Reset Meter
City of Mapleton, IA	Provided and Installed Ion Exchange for Nitrate Reduction/Bulk Salt Storage	400	Three (3) Fleck 3900 Multi-Port Control Valves	Demand Reset Meter
City of Dallas Center, IA	Provided and Installed Iron/Manganese Filtration and Ion Exchange for Softening	450	Aqua Matic Diaphragm Valves	Aqua Matic 962 Stager Control
City of Varina, IA	Provided and Installed Pressurized Aeration and Iron/Manganese Filtration	50	Five (5) 3150 Fleck Filter Control Valves	Two (2) Systemax 2000 Controllers
City of Sheridan, MO	Provided and Installed Iron/Manganese Filtration System	50	Manual	N/A
Lake View, Ia.	Installation of New Nitrate Removal System, Iron Removal, Aeration and controls.	350	Automatic	Allen Bradley
Twin Lakes Utilities	Provided and Installed Ion Exchange for Organic Reduction and Softening/Bulk Salt Storage	200	Five (5) Fleck 3900 Multi-Port Control Valves	Two (2) Systemax 2000 Controllers
Village of Sheffield, IL	Provided and Installed Iron/Manganese Filtration System	200	Manual	N/A

City of Albert City, IA	Installed Aeration and Iron/Manganese Filtration System	200	Manual	Allen Bradly
City of Holstein, IA	Refurbished Aeration and Iron/Manganese Filtration System	200	Manual	N/A
Park View Water Company	Provided and Installed Iron/Manganese Filtration System	400	Aqua Matic Diaphragm Valves	Aqua Matic 962 Stager Control
City of Adel, Ia	Removal and replacement of under bedding and filtration media in a 8' X 20' pressure filter.	300	Diaphragm Valves	N/A
City of Lanesboro, Ia	Provided and Installed pressurized aeration and pressurized iron/manganese filtration system.	75	Manual	N/A
City of Elkhorn, Ia.	Provided and installed new softener system.	200	Automatic	Aqua matic
City of Bancroft, Iowa	Installation of iron/Manganese Filtration System. 11' diameter tank	250	Manual	N/A
City of Corwith, Ia.	Installation of aerator, detention tank, high service pumps and iron removal pressure vessels.	80	Automatic	Allen Bradely
City of Gowrie, Ia	Removal and installation of 10' Diameter Iron/Manganese Removal System	250	Manual	Allen Bradley Controller
City of Glidden, Ia.	Removal and installation of 10' Diameter Iron/Manganese Removal System and Softener System	225	Manual Backwash valves for filter and Automatic control valves for softener.	Allen Bradley Controller
City of Swea City, Iowa	Removal and replacement of under bedding and filtration media in 10' Diameter iron filter	225	Manual	N/A
Kimballton, Ia.	Removal And Replacement of Greensand Media.	150	N/A	N/A
Coolidge, Ks	Provided Softener/Radium reduction System	100	Fleck 3200 NT Controller	N/A
Mooreland, Ia.	Provided Pressurized Oxidation/Retention & Filtration System	75	Aqua Matic Diaphragm Valves	N/A
Little Sioux, Ia.	Removal and replacement of filtration media.	50	N/A	N/A
Clay Rural Water	Provide Softener System and start-up	150	Fleck 3900	Systemax 2000 Controller
Westbend, Ia.	Removal and Replacement of Two Softeners and Hi Service	200	N/A	N/A

	Pumps			
Harlen, Ia. MU	Installation of Media, Air Scour System & Blower.	800	Roberts	N/A
Callander, Ia	Removal and replacement of Iron Filter	200	Existing	N/A
Harvey, Ia.	Media Replacement	50	N/A	N/A
Lytton, Ia	Removal and Replacement of Two (2) Water Softeners	200	Aqua Matic Diaphragm valves	Aqua Matic 962 Controller
North English, Ia.	Removal and Replacement of Two (2) Water Softeners	200	Aqua Matic Diaphragm valves	Aqua Matic 962 Controller
Woodward, Ia.	Installation of a Nitrification System, Piping, Valves, and Controller.	300	N/A	N/A
Chariton, Ia.	Installation of Baffle curtains and chemical feed equipment.	500	N/A	N/A
Danbury, Ia	Added Nitrate Selective Resin to existing system.	100	N/A	N/A
Emerson, Ia	Provided Nitrate Reduction System with Outside Bulk Salt Storage Tank.	200	3900 Fleck Control Valves	3200 NT Timer
Bloomfield, Ia	Replacement of media, Installation of MIOX, Control Valves and controller.	800	Electric Butterfly Valves	Allen Bradley
Oakville, Ia	Removal and replacement of filter media.	75	Manual Valves	N/A
Pomeroy, Ia.	Removed, Provided and Replaced the Iron Filtration Equipment	200	Manual Valves	N/A
Manchester, Ia.	Provided and installed Nitrate reduction system with pre filtration.	140	Butterfly Valves	Aqua matic 962 Controller
Auburn, Ia	Removal and replacement of Greensand and underbedding.	100	N/A	N/A
Armstrong, Ia	Removal and replacement filtration media, removal and replacement softening media, and provided and installed above ground bulk salt storage tank.	200	N/A	N/A
South Sioux City, NE	Removal and replacement of filter media for four high pressure filters		N/A	N/A